Statement showing the approximate quantities of work for constructing one block of quarters with a block of latrines at Malavalli.

Sl. No.	Description of item	Unit	Quantity in	
			Quarters	Latrine
1	Earthwork excavation including filling in basement.	C.yd.	44	4
2a	Concrete stone jelly in ordinary mortar ...	C.ft.	347	..
b	Coursed rubble stone masonry in clay, foundation and basement, including through stones at six feet intervals in every course.	"	986	130
c	Burnt brick in clay superstructure	"	2,070	..
d	Do in mortar do	"	352	196
e	Stone slabs 4" thick roughly dressed and fixed in mortar.	S.ft.	156	...
f	Stone pillars 4" thick including paly cutting and fixing in position.	"	26	..
g	Plain cornice 6" projection built of brick in mortar and chunam plastered complete.	R.ft.	75	...
h	Chunam plastering two coats	Square	52·16	4·91
i	Pointing with chunam mortar including thread lines.	"	1·00	0·56
j	White and colour washing, two coats	"	53·16	5·47
k	Binding wall $1\frac{1}{8}$" x $\frac{3}{4}$" brick in mortar and chunam plastered and white washed. ...	R.ft.	74	...
l	Chunam borders 6" x 3" over varandah roof ...	"	30	...
3	Flooring with 3" concrete and cement plaster $\frac{1}{4}$" thick well trowelled and finished smooth and even.	Square	8·20	...
4a	Roofing with 1st Class Mangalore tiles on teak reepers including wood oiling to reepers.	"	11·81	...
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	23	...
c	Ventilating tiles set in mortar	each	16	...
d	Mattywood work with wood oiling, two coats ...	C.ft.	41·50	...
e	Doors, teak wood frames with honne wood battened 1" thick shutters with fittings, etc., complete.	S.ft.	78	...
4f	Windows with teak wood frames and honne wood battened shutters 1" thick with iron bars 5/8" dia. and necessary fittings, etc., complete.	"	70	...
g	Ventilators with teak wood and glazed shutters fixed complete.	"	24	...
h	Chocolate painting, two coats	Square	3·55	...
i	Constructing sinks with drain pipes complete ...	Each	4	..
j	Providing stone mortar and pestle including fixing...	"	4	...
k	Galvanized iron sheet sun shade on teakwood battens with chocolate painting.	"	4	...
5	Flooring with 3" concrete bed with cement plastering $\frac{1}{2}$" thick on top.	Square	...	0·38
6	Cement plastering $\frac{1}{2}$" thick	"	...	0·79
7	Tar washing two coats ...	"	...	0·63
8	Fixing outlets from the latrine with drains complete.	1 item	...	Lump sum.
9	Providing galvanized iron sheet tubs 12" x 6" with handles, etc., complete with tarring	Each		6

V. R. COWSIK,
For *Chief Electrical Engineer.*

OFFICE OF THE DIRECTOR OF AGRICULTURE IN MYSORE, BANGALORE.

Notice No. Roc. 1382—*Sc.* 134 *of* 32-33, *dated* 26*th December* 1932.

Sealed tenders will be received in the office of the undersigned up to 12 noon on Friday the 27th January 1933 for the supply of spraying materials for the Mysore Agricultural Department.

For further particulars, please see page 19, Part VI of the *Mysore Gazette*, dated 5th January 1933.

K. BHIMA RAO,
For *Director of Agriculture.*